TEST REPORT					
250 Chester Street Painesville, Ohio 44077 Phone: 866-GO-AVERY (866-462-8379)	PRODUCT: SUPPORT: SUBSTRATE: CERT NO.:	FT 8397 EPDM FOAM PAINTED METAL 221213 - 0809		ANSI National Accreditati A C C C R E D L T ISO/IEC 17025	TED
Fax:888-358-4469email:psa.tape@averydennison.comURL:tapes.averydennison.com	FORD WSB M3 OEM Rev Date Tape, Low Den		TESTING LABORAT	ORY	
TAPE REQUIREMENTS:SECTION: 3.12Pressure Sensitive Adhes3.12.1, Adhesion to Stainless Steel	SION ASTM E	01000 <u>Specification</u> 500 N / m		<u>Results</u> 786.3	<u>Status</u> Pass
3.12.2, Adhesion to Painted Metal		500 N / m		642.7	Pass
SECTION 3.12 Adhesion to Stainless Sta 3.12.3, Adhesion, 30 mins @ 120°C, Inverted	eel	Specification No Adhesion Loss or Failur	9	<u>Results</u> Good, Stable, No Lifting	<u>Status</u> Pass
3.12.3, Adhesion, Environmental Cycling 5x, In 16 hrs @ 38°C / 95-100% 4 hrs @ -30C 4 hrs @ 90°C		No Adhesion Loss or Failur	9	Good, Stable, No Lifting	Pass
SECTION: 3.14 Fogging 3.14, 3 hrs @ 100°C, 21°C Cooling, 16 hrs @ I	SAE J1: RT	756 <u>Specification</u> 60 Units		<u>Results</u> 89.8	<u>Status</u> Pass
SECTION 3.15 Heat Shrink Resistance 3.15, 21 days @ 121°C, Painted Metal - % Heig	ht Loss	Specification < 10% All Directions	Height	<u>Results</u> 0%	<u>Status</u> Pass
3.15, 21 days @ 121°C, Painted Metal - % Heig	ht Loss	< 10% All Directions	Width	3%	Pass
3.15, 21 days @ 121ºC, Painted Metal - % Heig	ht Loss	< 10% All Directions	Length	2%	Pass
SECTION: 3.16 Liner Removal 3.16, Liner Removal, Initial, Room Temp	ASTM E	2 - 11 N / m		<u>Results</u> 8.8	<u>Status</u> Pass

Dave Nichols Jr, Automotive Lab Technician

CERTIFIED BY:

ISSUE DATE:

1-1-24

Materials tested to OEM requirements @ 72°F +/- 2°F and 50% RH +/- 5%. Test uncertainty and minor exclusions are available online or upon request. This certificate or report shall not be reproduced except in full, without the written approval of the Avery Dennison Performance Tapes. Status opinion based upon measurements obtained by personnel with appropriate training and professional experience. This laboratory is not accredited for the calibrations or tests marked *.

Avery Dennison Performance Tapes 250 Chester St. Painesville, Ohio 44077

