TEST REPORT					
250 Chester Street Painesville, Ohio 44077	PRODUCT: SUPPORT: SUBSTRATE: CERT NO.:	FT 8397 EPDM FOAM SS 221213 - 0809			
Phone: 866-GO-AVERY (866-462-8379) Fax: 888-358-4469 email: psa.tape@averydennison.com URL: tapes.averydennison.com	FORD WSB M3G212-A OEM Rev Date: Feb 06 Tape, Low Density EPDM Foam, Pressure Sensitve, Supe			TESTING LABORAT	ORY
TAPE REQUIREMENTS:SECTION: 3.12Pressure Sensitive Adhese3.12.1, Adhesion to Stainless Steel	Sion ASTM D10	000 <u>Specification</u> 500 N / m		<u>Results</u> 786.3	<u>Status</u> Pass
3.12.2, Adhesion to Painted Metal		500 N / m		642.7	Pass
SECTION 3.12 Adhesion to Stainless Sta 3.12.3, Adhesion, 30 mins @ 120°C, Inverted	eel	Specification No Adhesion Loss or Failure)	<u>Results</u> Good, Stable, No Lifting	<u>Status</u> Pass
3.12.3, Adhesion, Environmental Cycling 5x, Im 16 hrs @ 38°C / 95-100% 4 hrs @ -30C 4 hrs @ 90°C		No Adhesion Loss or Failure	3	Good, Stable, No Lifting	Pass
SECTION: 3.14 Fogging 3.14, 3 hrs @ 100°C, 21°C Cooling, 16 hrs @ F	SAE J175 RT	6 <u>Specification</u> 60 Units		<u>Results</u> 89.8	<u>Status</u> Pass
SECTION 3.15 Heat Shrink Resistance 3.15, 21 days @ 121°C, Painted Metal - % Heig	ht Loss	Specification < 10% All Directions	Height	Results 0%	<u>Status</u> Pass
3.15, 21 days @ 121ºC, Painted Metal - % Heig	ht Loss	< 10% All Directions	Width	3%	Pass
3.15, 21 days @ 121ºC, Painted Metal - % Heig	ht Loss	< 10% All Directions	Length	2%	Pass
SECTION: 3.16 Liner Removal 3.16, Liner Removal, Initial, Room Temp	ASTM D10	000 <u>Specification</u> 2 - 11 N / m		<u>Results</u> 8.8	<u>Status</u> Pass
\sim	11/				

CERTIFIED BY:

Dave Nichols Jr, Automotive Lab Technician

ISSUE DATE:

1-1-24

Materials tested to OEM requirements @ 72°F +/- 2°F and 50% RH +/- 5%. Test uncertainty and minor exclusions are available online or upon request. This certificate or report shall not be reproduced except in full, without the written approval of the Avery Dennison Performance Tapes. Status opinion based upon measurements obtained by personnel with appropriate training and professional experience. This laboratory is not accredited for the calibrations or tests marked *.

Avery Dennison Performance Tapes 250 Chester St. Painesville, Ohio 44077

